BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16517

APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Vidyaranyapura Suvarna Mahotsava Playground fencing and Development works in ward no. 09 of Vidyaranyapura sub division.

37

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of BHARATH ADITHYA V	
				In Figures	In Words
1	89.1	supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m.(extra lead charges will be paid separetly) etc complete as per	cum	261.95	Rupees Two Hundred Sixty One and Ninety Five Paise Only
2	44.55	Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4798.57	Rupees Four Thousand Seven Hundred Ninety Eight and Fifty Seven Paise Only
3	43.43	Providing and laying in position plain cement concrete of mix M 15 withOPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5274.36	Rupees Five Thousand Two Hundred Seventy Four and Thirty Six Paise Only
4	654	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts, cutting, bending wherever necessary, wastage and lapping etc complete as	sqm	675.73	Rupees Six Hundred Seventy Five and Seventy Three Paise Only
5	247.2	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead and lift and as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting. (excluding cost of earth work and concrete)etc complete as per specifications and directions	mtr	1103.41	Rupees One Thousand One Hundred Three and Forty One Paise Only
6	1585	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as	mtr	319.69	Rupees Three Hundred Nineteen and Sixty Nine Paise Only
7	1336.5	Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, etc complete as per specifications	Sqm	51.32	Rupees Fifty One and Thirty Two Paise Only

8	540	Fabricating, providing and erecting in poiston of M.S Ornamental security Grill Gate with out hot dip using75x12mm M.S flat for alround frame work with verticals at the centre and horizontal centere support M.S square of 20x20mm of different heights as shown in the draing are to be fixed at 16 cms c/c for square bars of full height and at 8cmsc/c for bottom rods providg ornamental CI designers at the botom and c I arrows in the middle and	kgs	149.69	Rupees One Hundred Forty Nine and Sixty Nine Paise Only
9	841.5	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	cum	145.41	Rupees One Hundred Forty Five and Forty One Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92